

Appendix-6

Horticulture Material Items

Sr. No.	Item Description	Unit	Rate
1	Compost and FYM (30 kg. Bag)	kg.	450.00
2	Supply of Pesticides, Fungicides and insacticides at site as per the instructions.	Ltr.	680.00
3	Supply and apply of jivamrut at specified site.	Ltr.	125.00
4	Supplying and planting of trees of specified variety attached here with seprate sheet in digging of Tree pit should be 2 cum prepared tree pit including pesticides, termite treatment with 10% Solution and planting of mature tree saplings (Bag size: 21x21, Height: 10 to 12 ft. and Stem thickness: 4 to 5 inch) with 70:30 ratio of garden soi and FYM and Organic manure @ 10%, Humic acid@ 10%, Castol cake @ 10% completed for each pit. Tree plantation should be carried on neatly accurately dieses free and fresh with healthy condition. Tree Saplings planted perfection as per drawing and instruction given by the Incharge of Garden Department. Plants shall be planted by manual/ mechanical means and rate shall be inclusive of all material labour, equipments as per description. Plant must be supply in bag size of 21" X 21" or above and each tree should have enough supporter. Plastic bags or pots should be removed carefully and soil around the roots should not be dropped or disturbed much. Rates for mortality to be inclusive. Work shall be done as shown in the drawing or as directed and approved by SRFDCL Garden Department.	Nos.	3747.00
4.1	Ficus religiosa-Pipal and other tree		
4.2	Azadirachta indica- Neem and other tree		
5	PLANTATION Supplying and planting fresh and healthy plants of 2-3 ft. Height with all material including transporting and labouring and all othe inclusive.	Nos.	85.00
6	Supplying of Garden soil shell be done in proper slope as per mention in below description including dressing etc. complete, as directed	cum	850.00
7	Supply of Support Stick/Protection having height of min. 8 to 10 feet for Tree Plantation at Road Side, Central Verge, Plot Area and Other	Nos.	175.00
8	Laying out Lawn: After excevation soil up to 30cm depth & removing unwanted stuff like stone etc. supplying & planting suckers of pure dharo. (Doob) grass of approved quality, roughly at 10x10 cm distance and mixing fill well established etc. completed.	Sq.mtr.	162.00
9	Supply saplings of Champa having height of minimum 8.00 to 12.00 ft. bagsize 21inchx21inch, well branched, well established & free from disease at site as per the instructions.	Nos.	3747

10	EXCAVATIONWORK The land for the landscape development shall be cleared of all waste vegetation other than the existing trees. The removal of existing roots of small plants and stumps shall be removed upto 90 cm. Removing debris of previously executed civil works upto 100mm depth wherever required as directed by EIC and disposing off the debris anywhere outside the site premise is required. The place of disposal shall be directed by engineer in-charge.	CUM	97
11	Disposing of the surplus excavated earth and/ or debris etc. including loading at site, transporting by mechanical or manual means & disposal, unloading, spreading and dressing and compacting with required capacity of roller as approved by engineer in charge beyond the initial lead of 50 m and lifts, etc complete. (Item shall be executed where disposal of earth is not included in relevant items)	CUM	215
12	Supply saplings of Bougainvillea sp. having height of minimum 3.00 to 5.00 ft. bag size 32 cm to 52 cm, well branched, well established & free from disease at site as per the instructions.		
12.1	Bougainvillea glabra, torch glory, formosa etc.	Nos.	450.00
13	SHRUBBERY PLANTATION: Supply well grown shrub plants and ground cover plants of average height 3' to 4' and planting	Sq.Mtr.	2925.00
14	Plantation Maintenace work (including watering, stacking, spraying, threding, weeding, hoeing, pruning, trimming)	Sq. Mtr./Year	620
15	Gheru colour for trees	Nos.	98.00
16	Tree guard repairing Removing tree guard by cutting 18 bolts and joint with 18 new bolts, Welding the broken frame and base of tree guard and other repairing work as per require	Nos.	749.00
17	Tree guard colouring Tree guard colouring work, material and labour charges as per require	Nos.	249.00
18	Supply of Water tanker for watering plants as per Instructions including all expence like Driver, Diesel etc.	Turn	733.00
19	Cocopeat	Ton	21750.00